

TEST PLAN

SPECTRUM CONTROL, INC.

Lot Acceptance Inspection Summary

Customer Name:	Customer Number:	File Number:	Revision Number:	Date Code:
Lot Number:		PPIR/ECN/Rev: 186852 / 00	PPIR/ECN Date 08/04/98	

Step:	Examination or Test Required	Pass	Fail	Comments:
1	VISUAL/MECHANICAL			0 Defect per Table II of IT 38-0185 Accept 0/Reject 1
	Perform visual/mechanical per MIL-PRF-15733.			
2	AUTO TEST			100%
	Cap: 3200 pF min., 8000 pF max. @ 1 KHz DF: 4% max @ 1 KHz DWV: 700 VDC IR: 1000 megohm @ 200 VDC Test per: MIL-STD-202, Method 301/302/305			